

भारतीय राष्ट्रीय राजमार्ग प्राधिकरण (सड़क परिवहन और राजमार्ग मंत्रालय) National Highways Authority of India (Ministry of Road Transport & Highways) क्षेत्रीय कार्यालय, मदुरे / Regional Office, Madurai दूसरा व तीसरी तल, विजय कृष्ण प्लाज़ा, संख्या-1 लेक एरिया, मेनूर मेन रोड, माहुतावनी, मदूरे-625 107 2rd & 3rd Floor, Vijay Krishna Plaza, No.1, Lake Area, Melur Main Road, Mattuthavani, Madurai-625 107



NHAI/15018/3.4.10/2021/ RO Madurai/E:114544/2237

20th November 2021

Invitation of Public Comments

Sub: NHAI, Madurai Region - Highway Administration - Permission for laying of underground OFC under PIU, Thanjavur - laying underground Optical Fiber Cable by M/s. Telosonic Networks Ltd (Airtel), Chennai Along the Road at from Km.60/250 to Km.69/505 (LHS) Total Length of 9255Mts (Existing Chainage) & from Km.65/960 to Km.66/000 (LHS), Km.74/650 to Km.75/000 (LHS), Km.74/670 to Km.95/000 (RHS), Km.75/500 to Km.75/690 (LHS), Km.90/100 to Km.90/540 (LHS), Km.95/000 to Km.95/435 (LHS) (Design Chainage) Crossing at across the road at Km. 75/000, Km. 75/500, Km. 90/100, Km. 95/000 on Sethiyathope - Cholapuram section of NH45C in the state of Tamilnadu.

- 1. A proposal was received from the <u>M/s. Telosonic Networks Ltd (Airtel), Chennai</u> regarding laying underground Optical Fiber Cable along the road from Km.60/250 to Km.69/505 (LHS) Total Length of 9255Mts (Existing Chainage) & from Km.65/960 to Km.66/000 (LHS), Km.74/650 to Km.75/000 (LHS), Km.74/670 to Km.95/000 (RHS), Km.75/500 to Km.75/690 (LHS), Km.90/100 to Km.90/540 (LHS), Km.95/000 to Km.95/435 (LHS) (Design Chainage) Crossing at across the road at Km. 75/000, Km. 75/500, Km. 90/100, Km. 95/000 by HDD method on on Sethiyathope Cholapuram section of NH45C in the state of Tamilnadu i.e., in a length of 31280m.
- 2. The proposed location are as hereunder:

s.	Village Name	Chainage in Km.		Side
No.		From	То	Side
1	Sethiyathope	60.250	69.505	LHS
2	Pinnalur	65.960	66.000	LHS
3	Mazhavarayanallur	74.650	75.000	LHS

		_	_	
4	Kothandavilagan	74.670	74.910	RHS
5	Nangudi	74.910	77.400	RHS
6	Nandeeswaramangalam	77.400	78.800	RHS
7	Cholatharam	78.800	81.230	RHS
8	Pudaiyur	81.230	82.380	RHS
9	Palayamkottai Keelpathi	82.380	83.080	RHS
10	Vanamadevi	83.080	84.050	RHS
11	Agaraputhur	84.050	85.180	RHS
12	Mamangalam	85.180	86.440	RHS
13	Karunakaranallur	86.440	87.660	RHS
14	Pappakudi (North)	87.660	89.430	RHS
15	Pappakudi (South)	89.430	91.730	RHS
16	Kundaveli (West)	91.730	93.730	RHS
17	Kundaveli (East)	93.730	95.000	RHS
18	Nangudi	75.500	75.690	LHS
19	Pappakudi (South)	90.100	90.540	LHS
20	Kundaveli (East)	95.000	95.435	LHS
21	Nangudi	75.000		Across
22	Nangudi	75.500		Across
23	Kundaveli (West)	90.100		Across
24	Kundaveli (East)	95.000		Across

3. Underground Optical Fiber Cable will be laid more than 1.65m below Ground Level as per the Ministry stipulation of minimum 1.20 meter below the ground level.

4. Crossing Proposed by trenchless method (HDD) with encasing OFC for the entire NH RoW. The encasing pipe will be laid at 1.65 below Ground Level as per the Ministry stipulation of minimum 1.20 meter below the ground level.

A copy of drawing showing proposed alignment is enclosed herewith for information.

Comments of the public on the above proposal are invited and the same may be communicated to

The Regional Officer,
National Highways Authority of India,
2nd & 3rd Floor, Vijay Krishna Plaza,
No.1.Lake Area, Melur Main Road
Mattuthavani, Madurai-625017.

This is issued with the Approval of Competent Authority

Yours Sincerely,

Encl: As Above.

(MS Chaithanya)
Manager (Tech)

Copy to:

- 1. The NIC, New Delhi for uploading in the Ministry's website
- 2. PD PIU Thanjavur.
- 3. M/s. Telosonic Networks Ltd (Airtel), No.42/147 & 44/146, Santhome High Road & Rosary Church Road, Mylapore, Chennai 600 004.