



सत्यमेव जयते

भारतीय राष्ट्रीय राजमार्ग प्राधिकरण (सड़क परिवहन और राजमार्ग मंत्रालय, भारत सरकार)) National Highways Authority of India (Ministry of Road Transport & Highways, Govt. of India)

क्षेत्रीय कार्यालय, ओडिशा / Regional Office, Odisha

301 - ए, तीसरी मंजिल, पाल हाईट्स, प्लॉट नं जे/ 7, जयदेव विहार, भुवनेश्वर - 751013, ओडिशा
301-A, 3rd Floor, Pal Heights, Plot No : J/7, Jayadev Vihar, Bhubaneswar- 751013, Odisha
दूरभाष / Ph.: 0674 - 2361470/ 570/670 (का/ओ), फैक्स / Fax : +91-674-2361770
ई-मेल / e-mail : roodisha@nhai.org, ronhaiodisha@gmail.com, वेबसाइट / Web : www.nhai.gov.in



NHAI/13011/54/RO/ODI/4200/2022

16.12.2022

To

The Sr. Technical Director,
NIC Centre at MoRTH,
Transport Bhawan,
New Delhi 110001

Sub: Four laning of Panikoli-Rimuli section of NH-215 (New NH-20) from Km.0.000 to Km.163.000 (Design Chainage Km.0.000 to Km.166.173) in the State of Odisha, 4-L of 145.123 Km currently under Operation & Maintenance Stage and 21.05 Km under implementation stage through balance work project-. **NOC proposal for ROW access permission for laying of 1 no. Iron Ore Slurry pipeline of Steel of dia 800mm for iron ore transportation, 1 no. return water pipeline of Steel of dia 800mm & 50mm dia OFC duct to Paradeep, Jagatsinghpur District from Ch.Km.0+000 at Panikoli Chhak to Ch.Km.79+500 at Golabandaha village (LHS), Ch.Km.79+500 at Golabandaha village to 113+430 at Jamunalia village (RHS) & Ch.Km.113+430 at Jamunalia village to Ch.Km.166+173 at Rimuli (LHS) with total as 166.173Km within the Utility Corridor along the road & 2 nos. of Crossing from LHS to RHS at Km.79+500 and RHS to LHS at Km. 113+430 across the road of NH-215 in Jajpur & Keonjhar District of Odisha State for underground Slurry pipeline project from proposed Greenfield 30 MTPA Beneficiation Plant at Deojhar, Keonjhar District to proposed 24 MTPA Greenfield Pellet Plant located at Bhitargarh, Paradip, Jagatsinghpur District as sought by the Authorised Signatory, M/s. Thriveni Earthmovers Private Limited, At:- 22/110, Greenways Road, Fairlands, Salem, Tamilnadu-636016 – reg**

Sir,

Please find enclosed herewith a proposal of M/s. Thriveni Earthmovers Private Limited, Tamilnadu for laying of 1 no. Iron Ore Slurry pipeline of Steel of dia 800mm for iron ore transportation, 1 no. return water pipeline of Steel of dia 800mm & 50mm dia OFC duct to Paradeep, Jagatsinghpur District from Ch.Km.0+000 at Panikoli Chhak to Ch.Km.79+500 at Golabandaha village (LHS), Ch.Km.79+500 at Golabandaha village to 113+430 at Jamunalia village (RHS) & Ch.Km.113+430 at Jamunalia village to Ch.Km.166+173 at Rimuli (LHS) with total as 166.173Km within the Utility Corridor along the road & 2 nos. of Crossing from LHS to RHS at Km.79+500 and RHS to LHS at Km. 113+430 across the road of NH-215 in Jajpur & Keonjhar District.

2. Accordingly, as per guidelines issued by MoRTH vide F. No. RW/NH-33044/29/2015/S&R(R) dt. 22.11.2016, the application along with the recommendations of concerned PD/Consultants are enclosed herewith with request to hoist the same in the Ministry's Website for public comments within 30 days of uploading on the website.

This is issued with the approval of the "Regional Officer, NHAI, Regional Office, Odisha, Bhubaneswa.

Yours faithfully,

(D.K. Patra)
Manager (Tech)



भारतीय राष्ट्रीय राजमार्ग प्राधिकरण

(सड़क परिवहन और राजमार्ग मंत्रालय, भारत सरकार)

National Highways Authority of India

(Ministry of Road Transport & Highways, Govt. of India)

क्षेत्रीय कार्यालय, ओडिशा / Regional Office, Odisha

301 - ए, तीसरी मंजिल, पाल हाईट्स, प्लॉट नं जे/ 7, जयदेव विहार, भुवनेश्वर - 751013, ओडिशा

301-A, 3rd Floor, Pal Heights, Plot No : J/7, Jayadev Vihar, Bhubaneswar- 751013, Odisha

दूरभाष / Ph.: 0674 - 2361470/ 570/670 (का/ओ), फैक्स / Fax : +91-674-2361770

ई-मेल/e-mail : roodisha@nhai.org, ronhaiodisha@gmail.com, वेबसाइट/Web : www.nhai.gov.in

सत्यमेव जयते



NHAI/13011/54/RO/OD/ 4199 /2022

16.12.2022

INVITATION OF PUBLIC COMMENTS

Sub: Four laning of Panikoili-Rimuli section of NH-215 (New NH-20) from Km.0.000 to Km.163.000 (Design Chainage Km.0.000 to Km.166.173) in the State of Odisha, 4-L of 145.123 Km currently under Operation & Maintenance Stage and 21.05 Km under implementation stage through balance work project-. **NOC proposal for ROW access permission for laying of 1 no. Iron Ore Slurry pipeline of Steel of dia 800mm for iron ore transportation, 1 no. return water pipeline of Steel of dia 800mm & 50mm dia OFC duct to Paradeep, Jagatsinghpur District from Ch.Km.0+000 at Panikoili Chhak to Ch.Km.79+500 at Golabandaha village (LHS), Ch.Km.79+500 at Golabandaha village to 113+430 at Jamunalia village (RHS) & Ch.Km.113+430 at Jamunalia village to Ch.Km.166+173 at Rimuli (LHS) with total as 166.173Km within the Utility Corridor along the road & 2 nos. of Crossing from LHS to RHS at Km.79+500 and RHS to LHS at Km. 113+430 across the road of NH-215 in Jajpur & Keonjhar District of Odisha State for underground Slurry pipeline project from proposed Greenfield 30 MTPA Beneficiation Plant at Deojhar, Keonjhar District to proposed 24 MTPA Greenfield Pellet Plant located at Bhitargarh, Paradip, Jagatsinghpur District as sought by the Authorised Signatory, M/s. Thriveni Earthmovers Private Limited, At:- 22/110, Greenways Road, Fairlands, Salem, Tamilnadu-636016 – reg**

M/s. Thriveni Earthmovers Private Limited, Tamilnadu has submitted a proposal laying of 1 no. Iron Ore Slurry pipeline of Steel of dia 800mm for iron ore transportation, 1 no. return water pipeline of Steel of dia 800mm & 50mm dia OFC duct to Paradeep, Jagatsinghpur District from Ch.Km.0+000 at Panikoili Chhak to Ch.Km.79+500 at Golabandaha village (LHS), Ch.Km.79+500 at Golabandaha village to 113+430 at Jamunalia village (RHS) & Ch.Km.113+430 at Jamunalia village to Ch.Km.166+173 at Rimuli (LHS) with total as 166.173Km within the Utility Corridor along the road & 2 nos. of Crossing from LHS to RHS at Km.79+500 and RHS to LHS at Km. 113+430 across the road of NH-215 in Jajpur & Keonjhar District.

2. As per guidelines issued by MoRTH vide F. No. RW/NH-33044/29/2015/S&R(R) dated 22.11.2016, the Highway Administration will put out the application in the public domain for 30 days for seeking claims and objections (on grounds of public inconvenience, safety and general public interest).

3. In view of the above, the comments of public, if any, on the above mentioned proposal is invited on below mentioned address:

The Regional Officer,
National Highways Authority of India,
Regional Office, Odisha
301-A, 3rd Floor, Pal Heights,
J/7, Jayadev Vihar, Bhubaneswar 751013, Odisha
e-mail : roodisha@nhai.org

This is issued with the approval of the "Regional Officer, NHAI, Regional Office, Odisha, Bhubaneswar".

(D.K. Patra)

Manager (Tech)

National Highways Authority of India,

Regional Office, Odisha

301-A, 3rd Floor, Pal Heights,

J/7, Jayadev Vihar, Bhubaneswar 751013

[Signature]
16/12/22

THRIVENI EARTHMOVERS PVT. LTD.

22/110, GREENWAYS ROAD, FAIRIANDS, SALEM - 636016, TAMILNADU, INDIA

Seeking ROW from Panikoili (00.000 Km) to Rimuli (166.173 Km) on NH-215 (Revised NH-20)

CHECK -LIST

Guidelines for Project Directors for processing the proposal for laying of 0.8M dia Iron Ore Slurry Pipeline And 0.8M dia Return Water Pipeline with OFC 50mm Dia along NH-215(New NH20)

Relevant Circulars

- 1) Ministry Circular No. NH-41 (58)/68 dated 31.01.1969
- 2) Ministry Circular No. NH-3/P/66/76 dated 18/19 .11.1976
- 3) Ministry Circular No. RW/NH/-3/P/66/76 dated 11.05.1982
- 4) Ministry Circular No. RW/NH-11037/1/66-DOI (2) dated 28.07.1993
- 5) Ministry Circular No. RW/NH-11037/1/86/DOI dated 19.01.1995
- 6) Ministry Circular No. RW/NH-34066/2/95/S&R dated 25.10.1999
- 7) Ministry Circular No. RW/NH-34066/7/2003 S&R (B) dated 17.09.2003
- 8) Ministry Circular No. Rw/NH-33044/29/2015/S&R* dtd 22.11.16

Check list for approval for laying of Iron Ore Slurry Pipelines on NH ROW Land

SL.No.	Item	Information/Status	Remarks
1	General Information	Thriveni Earthmovers Pvt Ltd has proposed to carry 30 MTPA Iron ore from Deojhar to Paradeep in Slurry form by laying 0.8 M dia iron ore slurry pipeline and 0.8M dia return water pipeline with 50mm dia OFC. In this context and with the available ROW width, seeking permission for laying 0.8M dia iron ore slurry pipeline and 0.8M dia return water pipeline with 50mm dia OFC along National Highway No-215(Revised NH20) from Panikoili (Chainage 00+000) to Rimuli (Chainage 166+173) by Open Trench method in general & Horizontal Directional Drilling (HDD) method at specific location like River,Bridge,Canal,Road,Railway...etc & places where locational constraint exist.	
1.1	Name and Address of the Applicant/Agency	M/s Thriveni Earthmovers Pvt Ltd 22/110, Greenways Road, Fairiands, Salem - 636016, Tamilnadu, INDIA	
1.2	National highway No-	NH 215 (New NH20)	
1.3	State	Odisha	
1.4	Location	Panikoili to Rimuli	
1.5	Chainage in km	CH 00+000 km to CH 166+173 (00.00 km to 79.500 km on LHS, 79.500 km to 113.430 km on RHS & 113.430 km to 166.173 km on LHS)	
1.6	Length in Meters	166173	
1.7	Width of available ROW	60 mtr (in general)	


For THRIVENI EARTHMOVERS PVT. LTD.

Authorised Signatory

SL.No.	Item	Information/Status	Remarks
	(a) Left side from center line towards increasing chainage/km direction	30 mtr	
	(b) Right side from centre line towards increasing chainage /km direction	30 mtr	
1.8	Proposal to lay underground pipes/electrical/FOC cables	Iron Ore Slurry Pipe 800mm dia & Return water pipe 800mm dia with 50mm dia fibre optic cable laying in the same pipeline trench	
	(a) Left side from center line towards increasing chainage/km direction	Beyond 25 m from CL as per ROW availability (00.000 km to 79.500 km & 113.430 km to 166.173 km on LHS)	
	(b) Right side from centre line towards increasing chainage /km direction	Beyond 25 m from CL as per ROW availability (79.500 km to 113.430 km on RHS)	
1.9	Proposal to acquire land	N/A	
	(a) Left side from center line	No	
	(b) Right side from centre line	No	
1.10	Whether proposal is in the same side where land is to be acquired	N/A	
	If not then where to lay the Pipeline	In the utility corridor of NHAI ROW	
1.11	Details of already laid services, if any ,along the proposed route	Yes, existing laid services considered in the cross sectional drawings & documents attached	
1.12	Number of lanes (2/4/6/8) existing	Existing 4 lanes	
1.13	Proposed number of lanes (2 lane with paved shoulders/4/6/8 lanes)	N/A	
1.14	Service road existing or not		
	If yes then which side	Yes	
	(a) Left side from center line towards increasing chainage/Km direction	Existing service road varies from 14m to 30m from centre line of road	Details attached in Annexure
	(b) Right side from center line	Existing service road varies from 14m to 30m from centre line of road	Details attached in Annexure
1.15	Proposed Service road	Yes	
	(a) Left side from center line	Proposed service road varies from 14m to 30m from centre line of road	Details attached in Annexure
	(b) Right side from center line	Proposed service road varies from 14m to 30m from centre line of road	Details attached in Annexure
1.16	Whether proposal to lay Iron Ore Slurry pipelines are after the service road or between the service road and main carriageway	Below the service road using RCC duct of 7.0 mtr wide and 2.23 mtr minimum depth from FRL of service road. Details drawing attached herewith	


(RE)




(Site Engineer)
MSU-KR

For THRIVENI EARTHMOVERS PVT. LTD.


Authorised Signatory

SL.No.	Item	Information/Status	Remarks
1.17	The permission for laying of Iron Ore Slurry pipeline shall be considered for approval/rejection based on the ministry circulars mentioned as above.	Yes, agreed	
	a) Carrying of Iron Ore Slurry pipeline on Bridges shall not be permitted as fumes/gases pipe can accelerate the process of corrosion or may be cause explosion, thus being much more injurious than leakage of water	Yes, agreed for not carrying Iron Ore Slurry pipelines on Bridges (Undertaking Attached)	
	b) Carrying of water Pipe lines on Bridges shall also be discouraged. However, if the water supply authorities seem to have no other viable alternative and approach the Highway Authority well in time before the design of the bridge is finalised, they may be permitted to carry the pipe line on independent superstructure, supported on extended portions of piers and abutments in such a manner that in the final arrangement enough free space around the superstructure of the bridge remains available for the inspection and repairs etc.	Yes, agreed for not carrying Iron Ore/Return water pipelines on Bridges but over independent superstructure if required with permission of Authority	
	(c) Cost of required extension of the substructure as well as that of the supporting superstructure shall be borne by the agency-in-charge of the utilities	Yes, agreed to comply	
	(d) Services are not being allowed indiscriminately on the parapet/any part of the bridges, safety of the bridges has to be kept in view while permitting various services along bridge. Approvals are to be accorded in this regard with the concurrence of the Ministry's Project Chief Engineers only	Yes, agreed to comply	


(RE)

Stimant

For THRIVENI EARTHMOVERS PVT. LTD.


Authorised Signatory




(Site Engineer)
PSU-192

SL.No.	Item	Information/Status	Remarks
1.18	If crossings of the road involved - If Yes , it shall be either encased in pipes or through structure or conduits specially built for the purpose at the expenses of the agency owning the line	Yes , crossing involved and it shall be encased with 2 Numbers of MS 1200mm dia pipes at our cost for each crossing location. (Two number of crossing at 79.500km & 113.430 km)	
	(a) Existing drainage structures shall not be allowed to carry the lines.	Yes, agreed to comply	
	(b) Is it on the line normal to NH	Yes	
	(c) Crossing shall not be too near the existing structures on the National Highway, the minimum distance being 15 M. What is the distance from the existing structures.	Distance from the nearest existing structures is beyond 15m	
	(d) The casing pipe (or conduit pipe in case of electric cable) carrying the utility line shall be of steel, cast iron, or reinforced cement concrete and have adequate strength and be large enough to permit ready withdrawal of the carrier pipe/cable.	Yes, agreed and Casing pipe material to be used is MILD STEEL PIPE of 1200mm dia for carrying Iron ore slurry pipeline of 800mm dai and return water pipeline of 800mm dia with conduit pipe for fibre optic cable	
	(e) Ends of the casing /conduit pipe shall be sealed from the outside , so that it does not act as a drainage path	Yes, agreed to comply	
	(f) The casing/conduit pipe should ,as minimum extend from drain to drain in cuts and toe of slope to toe of slope in the fills.	Yes, agreed to comply	
	(g) The top of the casing /conduit pipe should be at least 1.2 meter below the surface of the road subject to being at least 0.3 M below the drain inverts.	Yes, agreed to comply	
	(h) Crossing shall be boring method (HDD) specially where the existing road pavement is of cement concrete or dense bituminous concrete type.	Yes, crossing will be done by HDD method	
	(i) The casing/conduit pipe shall be installed with an even bearing throughout its length and in such a manner as to prevent the formation of water way along it.	Yes, agreed to comply	

HDD Technology will be adopted with casing pipes if required for specified locations along the road as per ROW statement, drawings, below structures, hindrances, etc

For THRIVENI EARTHMOVERS PVT. LTD.

Authorised Signatory

SL.No.	Item	Information/Status	Remarks
2	Document/drawings enclosed with the proposal	Yes, drawing, documents, enclosed	
2.1	Cross section showing the size of trench for open trenching method (Is it normal size of 1.2m deep X 0.3m wide)	Not normal size but as per drawing attached	
	(i) Should not be greater than 60 Cm wider than the outer diameter of the pipe	Yes, agreed to comply	
	(ii) located as close to the extreme edge of the right- of-way as possible but not less than 15 meter from the center lines of the nearest carriageway	Yes, agreed to comply	
	(iii) Shall not be permitted to run along the National Highways when the road formation is situated in double cutting .Nor shall these be laid over the existing culverts and bridges.	Yes, agreed to comply	
	(d) These should be so laid that their top is at least 0.6 m below the ground level so as not to obstruct drainage of the road land	Yes, agreed to comply	
2.2	Cross section showing the size of pit and location of pipeline for HDD method	Yes, Submitted as incorporated in the drawing and attached methodology	
2.3	Strip plan/ route plan showing pipeline ,chainage, width of ROW, distance of proposed , pipeline from the edge of ROW ,important milestone , intersections, cross drainage works etc.	Yes, submitted showing all desired details in the drawings	
2.4	Methodology for laying Iron Ore Slurry pipeline	Yes, Submitted	
2.4.1	Open trenching method (may be allowed in utility corridor only where pavement is neither cement concrete nor dense bituminous concrete type .If yes, Methodology of refilling of trench	Yes, open trenching allowed as per submitted methodology at specific locations as per available ROW statement & attached drawings, further compliance by Thriveni as per MORTH/IRC guidelines and NHAI instructions for such site requirment	
	(a) The trench width should be atleast 30 cm, but not more than 60 cm wider than the outer diameter of pipe	Yes, agreed to comply	

For THRIVENI EARTHMOVERS PVT. LTD.

Authorised Signatory


SL.No.	Item	Information/Status	Remarks
	(b) For filling of the trench ,Bedding should be a depth of not less than 30 cm. It shall consists of granular materials ,free of lumps,clods and cobbles and graded to yield a firm surface without sudden change in the bearing value. Unsuitable soil and rock edged should be excavated and replaced by selected material.	Yes, agreed to comply	
	(c) The backfill shall be completed in two stages (i)side-fill to the level of the top of the pipe and (ii) overfill to the bottom of road crust.	Yes, agreed to comply	
	(d) The side fill shall consist of granular material laid in 15 cm layers each consolidated by mechanical tampering and controlled addition of moisture to 95% of the proctor's Density. Overfill shall be compacted to the same density as the material that had been removed . Consolidation by saturation or ponding will not be permitted.	Yes, agreed to comply	
	(e) The road crust shall be build to the same strength as the existing crust on either side of the trench. Care shall be taken to avoid the formation of a dip at the trench.	Yes, agreed to comply	
	(f) The excavation shall be protected by flagman , signs and barricades , and red lights during night hours.	Yes, agreed to comply	
	(g) If required , a diversion shall be constructed at the expense of the agency owning the utility line	Yes, agreed to comply	
2.4.2	Horizontal Directional Drilling (HDD) Method	Yes, HDD method allowed as per submitted methodology at specific locations as per available ROW statement & attached drawings, further compliance by Thriveni as per MoRTH/IRC guidelines and NHAI instructions for such site requrement	


(RE)




(Site Engin)
PSV - 494

For THRIVENI EARTHMOVERS PVT. LTD.


Authorised Signatory

SL.No.	Item	Information/Status	Remarks
2.4.3	Laying of Iron Ore Slurry pipeline through CD works and method of laying	At all CD work locations HDD method will be adopted	
	(a) On approaches, the water mains/cables shall be carried along a line as close to the edge of the right-of-way as possible up to a distance of 30 m from the bridge and subject to all other stipulations contained in this Ministry's guidelines issued with letter No. H1/P/66/76 dated 19.11.1976.	Yes, agreed to comply	
3	Draft License Agreement signed by two witnesses	Yes, submitted	
4	Performance Bank Guarantee in favour of NHAI has to be obtained @ Rs.50/- per running meter (parallel to NH) and Rs. 1,00,000/- per crossing of NH, for a period of one year initially (extendable if required till satisfactory completion of work) as a security for ensuring/making good the excavated trench for laying the cables/ducts by proper filling and compaction, clearing debris/loose earth produced due to excavation of trenching at least 50 m away from the edge of the right of way. No payment shall be payable by the NHAI to the licensee for clearing debris/loose earth.	Yes, agreed for submission of Performance BG as per latest MoRTH / NHAI guidelines when asked by NHAI	
4.1	Performance BG as per above is to be obtained	Yes, agreed for submission when intimated by NHAI	
4.2	Confirmation of BG has been obtained as per NHAI guidelines	Yes, will be obtained after submission of BG	
5	Affidavit/Undertaking from the applicant for	yes, agreed & submitted	
5.1	Not to damage to other utility, if damaged then to pay the losses either to NHAI or to the concerned agency	Yes, agreed to comply & submitted undertaking	
5.2	Renewal of Bank Guarantee	Yes, agreed to comply & submitted undertaking	
5.3	Confirming all standard condition of NHAI's guideline	Yes, agreed to comply & submitted undertaking	
5.4	Shifting of Iron Ore Slurry pipeline as and when required by NHAI at our own cost	Yes, agreed to comply & submitted undertaking	
5.5	Shifting due to lanning/widening of NH	Yes, agreed to comply & submitted undertaking	

For THRIVENI EARTHMOVERS PVT. LTD.

Authorised Signatory


SL.No.	Item	Information/Status	Remarks
5.6	Indemnity against all damages and claims clause (24)	Yes, agreed to comply & submitted undertaking	
5.7	Traffic movement during laying of Iron ore slurry pipeline to be managed by the applicant	Yes, agreed to comply & submitted undertaking	
5.8	If any claim is raised by the concessionaire then the same has to be paid by the applicant	Yes, agreed to comply & submitted undertaking	
5.9	Prior approval of the NHAI shall be obtained before undertaking any work of installation, shifting or repairs, or alterations to the showing Iron Ore Slurry pipeline located in the National Highway right-of-way	Yes, agreed to comply & submitted undertaking	
5.10	Expenditure if any, incurred by NHAI for repairing any damage caused to the National Highway by the laying, maintenance or shifting of the Iron ore slurry pipeline will be done by the agency owning the line	Yes, agreed to comply & submitted undertaking	
5.11	If the NHAI considers it necessary in future to move the utility line for any work of improvement or repairs to the road, it will be carried out as desired by the NHAI at the cost of the agency owning the utility line within a reasonable time (not exceeding 60 days) of the intimation given.	Yes, agreed to comply & submitted undertaking	
5.12	Certificate from the applicant in the following format (1) Laying of Iron ore slurry pipelines will not have any deleterious effects on any of the bridge components and roadway safety for traffic (2) for 6 lanning "we do undertake that I will relocate service road/approach road/utilities at my own cost not withstanding the permission granted within such time as will be stipulated by NHAI for future six-lanning or any other development"	Yes, agreed to comply & submitted undertaking	
6	Who will sign the agreement on behalf of Iron Ore Slurry pipelines agency	Mr. Rajendra Kumar Mittal Authorised Signatory as appointed by Thriveni Earthmovers Pvt. Limited and Power of Attorney attached M/s Thriveni Earthmovers Pvt Ltd 22/110, Greenways Road, Fairlands, Salem - 636016, Tamilnadu, INDIA	

SL.No.	Item	Information/Status	Remarks
7	Certificate from the project director	Attached	
7.1	Certificate for confirming of all standard condition issued vide Ministry Circular No. NH-41(58)/(68) dated 31.1.1969, Ministry Circular No. NH-3/P/66/76 dated 18/19.11.1976 , Ministry Circular No. RW/NH-3/P/66/76 dated 11.5.1982 , Ministry Circular No. RW/NH-11037/1/86-DOI (2) dated 28.7.1993, Ministry Circular No. RW/NH-11037/1/86-DOI dated 19.1.1995, Ministry Circular No. RW/NH-34066/2/95/S&R dated 25.10.1999 and Ministry Circular No. RW/NH-34066/7/2003 S&R(B) dated 17.9.2003	Yes, Attached	
7.2	Certificate from PD in the following format (1)"It is certified that any other location of the Iron Ore Slurry pipelines would be extremely difficult and unreasonable costly and the installation of Iron Ore Slurry within ROW will not adversely affect the design, stability & traffic safety of the highway nor the likely future improvement such as widening of the carriageway ,easing of curve etc. " (2) for six-lanning (a) where feasibility is available " I do certify that there will be no hindrance to proposed six lanning based on the feasibility report considering proposed structures at the said location " (b) in case feasibility report is not available" I do certify that sufficient ROW is available at site for accommodating proposed six-lanning.	Attached	


(P.D.)



For THRIVENI EARTHMOVERS PVT. LTD.


Authorised Signatory




(Site Engineer)
P.D.-19

SL.No.	Item	Information/Status	Remarks
8	If NH section proposed to be taken up by NHAI on BOT basis- a clause is to be inserted in the agreement . " The permitted Highway on which Licensee has been granted the right to lay cable/duct/lay Iron Ore Slurry pipeline has also been granted as a right of way to the concessionaire under the concession agreement may likely to be handed over to the concessionaire for up-gradation of.....[section from Km.....of NH No.....on build ,Operate and Transfer Basis] and therefore , the licensee shall honour the same. "	Not applicable	
9	who will supervise the work of laying Iron Ore Slurry pipeline	M/s Thriveni Earthmovers Pvt Ltd 22/110, Greenways Road, Fairlands, Salem - 636016, Tamilnadu, INDIA, E-mail Id- ral@thriveni.com, Mob- 9437494989	
10	Who will ensure that the defects in road portion after laying of Iron Ore Slurry pipeline are corrected and if not corrected then what action will be taken.	M/s Thriveni Earthmovers Pvt Ltd 22/110, Greenways Road, Fairlands, Salem - 636016, Tamilnadu, INDIA, E-mail Id- ral@thriveni.com, Mob- 9437494989	
11	Who will pay the claims for damages done/disruption in working of concessionaire if asked by the concessionaire.	M/s Thriveni Earthmovers Pvt Ltd 22/110, Greenways Road, Fairlands, Salem - 636016, Tamilnadu, INDIA, E mail Id- ral@thriveni.com, Mob- 9437494989	
12	A certificate from PD that he will enter the proposed permission in the register of records of the permissions in the prescribed proforma (copy enclosed).	Yes, attached	
13	If any previous approval is accorded for laying of underground Iron Ore Slurry pipeline then photocopy of register of records of permissions accorded as maintained by PD then copy be enclosed	Yes, enclosed	



(Nayal)



For THRIVENI EARTHMOVERS PVT. LTD.


Authorised Signatory




(Site Engineer)
PJ U - Kyr.